VISTARA INTERIOR'S

Designing Dreams Creating Reality.....

Office Address: Office No.01, Ambekar Hotel Chowk, Undri Pisoli, Pune-411060

Contact: +91 7720097476/8482946451 Email: teamvistarainteriors@gmail.com

Date: 17/03/2026 Quotation No: 1125

CLIENT DETAILS

Client Name: Almas Shaikh Mam

Contact: +91 9552527376

Billing Address: Alina Living NIBM Pune 411048

2 BHK INTERIOR DESIGN

1. SCOPE OF WORK

SR .NO	Particular	Size
	ENTERANCE	
1	Safety Door With CNC Jali + Europa Lock	7 X 3
2	Name Plate	Led Name Plate
3	Shoe Rack	3 X 3
4	Entrance Paneling	9 X 3 & 2 X 3
5	Foyer Unit	3.5 X 9
6	Foyer Ceiling CNC Cutting	4 X 4
	LIVING ROOM	
1	Tv Unit	7 X 9
2	Sofa	6 Seater

3	Center Table (Glass Top)	2 X 3
4	Sofa Back Wall Designing (Molding / Wallpaper / Artifacts)	Entire Wall
5	A/c Pelmet	-
6	Balcony Pipe Cover	-
7	Balcony Grass Lawn	-
8	Vertical Garden	-
9	Sitout	5.6 X 2
10	Bedroom Enter Chaukat Paneling Round	-
11	Camera In Living Room	1
	KITCHEN	
1	Modular Kitchen With Tandem Box (European Theme)	13 X 2.8 + 7 X 2.8
2	Loft	2 X 13 + 2 X 13
3	Over Head Storage With Profile Light	2 X 13 + 2 X 7
4	Tall Unit For Oven, Mixer	2 X 7
5	Pantry Unit	2 X 7
6	Chaukat Paneling Round	-
	DINING AREA	
1	Dining Table Marble Top	6 Seater
2	Dining Wall Designing Diamond Glass Paneling	7 X 9
	MASTER BEDROOM	
1	Bed With Hydraulic Storage	6 X 6.6
2	Bed Back Cushion	2 X 6
3	Bed Back Wall Paneling	8 X 6
4	Bed Side Table	1.5 X 2 X 2
5	Wardrobe	8 X 7
6	Loft	2 X 11
7	Dressing Unit with Mirror	2 X 6
8	TV Unit Provision	-
9	A/c Pelmet	-
10	Balcony Pipe Cover	-
11	Vertical Garden	-
	KIDS BEDROOM	
1	Sofa Cum Bed	6 X 3 + 3
2	Bed Side Table	1.5 X 2
3	Wardrobe	7 X 7
4	Loft	10 X 2
5	Study Table Platform	2 X 3
6	Study Table Overhead Storage with Profile Light	3 X 3
7	Balcony Sit out With Cushion	5.6 X 2
8	A/c Pelmet	-
9	Dressing Mirror	2 X 7

	BATHROOMS	
1	PVC Ceiling Both Bathrooms	8 X 5 X 2
2	Glass Partitions Both Bathroom	3 X 9 X 2
3	Commode Change Both Bathrooms	Cera
	OTHER WORK	
1	False Ceiling Work	Entire Flat
2	Electrical Work (As Per Design)	Entire Flat
3	Painting Work	Entire Flat
4	Touch Switches & Alexa	Entire Flat
	CIVIL WORK	
1	Kitchen Demolish	Entire Kitchen
2	Kitchen Dado Tile Change	2 X 4
3	Kitchen Counter Top Change (Full Body Tile)	Parallel Counter Top
4	Bathroom 1 Wall Dado Tile Change	As Per Requirement
5	Plumbing Work	As Per Requirement
6	Bathroom Shower Fitting	As Per Requirement

COMPLETE INTERIOR TOTAL BUDGET – APPROX. Rs 18, 73,960 / -

AMOUNT IN WORDS –Eighteen Lac Seventy Three Thousand Nine Hundred And Sixty Only

2. MATERIAL SPECIFICATION

SR .NO	MATERIAL	BRAND
	PLAYWOOD	
1	Furniture: Redcore / Gurjan Plywood	BWR ISI710 GRADE (18mm & 12mm)
2	Kitchen: Redcore / Gurjan Plywood	BWP ISI710 GRADE (18mm & 12mm)
3	Safety door : Gurjan / Pine	BLOCK BOARD (35mm)
	HARDWARE	
1	Hardware : Premium Quality	ONYX (All Hardware Soft Close)
	LAMINATE	
1	Laminate	ADVANCE / Real Touch
	FALSE CEILING	
1	False Ceiling	GYPROC Gypsum Sheet
2	Pvc Ceiling	PVC BOARD

	ELECTRICAL	
1	Wire	POLYCAB WIRES,
2	Switches	LEGRAND SWITCHES (Electrical point As Per Design)
	LIGHTS	
1	Lights	CROMPTON OR ORIENT Panel Light + Cob lights + Profile Light
	PAINTS	
2	Paints:	ASIAN ROYAL (Wall Putty+ Primer +2 Coat)
	TILE AND COUNTER TOP	
1	Dado Tile 2X4	For Kitchen , Bathroom
2	Kitchen Counter Top (Parallel)	Full Body Tile

3. DESIGN & EXECUTION

2D & 3D Designing & Visualization

Material Selection Assistance

On-site Supervision

Installation & Finishing Work

Project Timeline: 65–70 Days

4. WHY CHOOSE VISTARA INTERIORS?

Transparent Pricing – No Hidden Charges

High-Quality Materials & Craftsmanship

Personalized Design with 3D Views

10-Year Warranty on Workmanship

Professional Team with End-to-End Supports

Deep Cleaning will provided by us

5. TERMS & CONDITIONS

Quotation subject to revision based on final 3D design.

Standard wardrobe modules included; extra drawers at additional cost.

Warranty will not be applicable for physical damage.

THANK YOU!

For any queries, feel free to contact us.

TEAM VISTARA INTERIORS

VISTARA
INTERIORS