VISTARA INTERIOR'S

Designing Dreams Creating Reality.....

Office Address: Office No.01, Ambekar Hotel Chowk, Undri Pisoli, Pune-411060

Contact: +91 7720097476/8482946451 Email: teamvistarainteriors@gmail.com

Date: 17/03/2026 Quotation No: 1238

CLIENT DETAILS

Client Name: Mr. Chandan Dhamale Sir

Contact: +91 9850872330

Billing Address: 57 Midtown Wakad Pune

3 BHK INTERIOR DESIGN

SCOPE OF WORK

SR .NO	Particular	Size
	ENTERANCE	
1	Safety Door With CNC Jali + Europa Lock	7 X 3
2	Shoe Rack With Seating	4 X 3
3	Vertical Storage	6 X 2
4	Entrance Paneling	9 X 3 & 2 X 3
5	Foyer Storage	6.2 X 3
6	Foyer Design	Molding/ Wall Paper /Artifacts
	LIVING ROOM	
1	Tv Unit	10 X 10
2	Temple Unit Frame	3 X 6
3	Designer Sofa	3 + 2 + 2 Seater

4	Vertical Storage	5 X 9
5	Dining Back Wall Design	Molding/ Wall Paper /Artifacts
6	Dining Table Marble Top	6 Seater
	MASTER BEDROOM	
1	Bed With Hydraulic Storage with bed back Cushion	6 X 6.6
2	Bed Back Wall Design	Molding / Wall Paper/Artifacts
3	Bed Side Table	1.6 X 2 X 2
4	Wardrobe	8 X 9
5	Dressing Unit with Mirror	2 X 7
6	Work Station With over Head Shelf With Profile Light	4 X 2
7	TV Unit Provision	-
	KIDS BEDROOM	
1	Bed With Hydraulic Storage + Bed Back Cushion	5.6 X 6
2	Bed Side Table	1.6 X 2 X 2
3	Bed Back Wall Design	Molding/ Wall Paper /Artifacts
4	Wardrobe	7 X 7
5	Loft Storage	2 X 7
6	Study Table	2 X 3
7	Study Over Head Storage	3 X 3
	PARENT BEDROOM	
1	Bed With Hydraulic Storage + Bed Back Cushion	6 X 6.6
3	Bed Side Table	1.6 X 2 X 2
4	Wardrobe	7 X 7
5	Loft	2 X 7
	BATHROOM	
1	Common Bathroom Vanity + Mirror	-
2	Other Bathrooms Vanity Storage	-
3	All Bathrooms Pvc Ceiling	-
	OTHER WORK	
1	False Ceiling Work	Entire Flat
2	Electrical Work (As Per Design)	Entire Flat
3	Painting Work	Entire Flat

COMPLETE INTERIOR TOTAL BUDGET – APPROX. 13, 68,960/

AMOUNT IN WORDS- Thirteen Lac Sixty Eight Thousand Nine Hundred and Sixty Only

MATERIAL SPECIFICATION

SR .NO	MATERIAL	BRAND
	PLAYWOOD	
1	Furniture: Gurjan Plywood	BWR ISI710 GRADE (18mm & 12mm)
2	Kitchen: Gurjan Plywood	BWP ISI710 GRADE (18mm & 12mm)
3	Safety door : Gurjan	BLOCK BOARD (35mm)
	HARDWARE	
1	Hardware : Premium Quality	ONYX
	LAMINATE	
1	Laminate	ADVANCE / REAL TOUCH
	FALSE CEILING	
1	False Ceiling:	GYPROC GYPSUM SHEET
2	Pvc Ceiling	PVC BOARD
	WALL DESIGNING	
1	Molding	POP / PVC
2	Wall Paper	WASHABLE PREMIUM
	ELECTRICAL	
1	Wire	POLYCAB WIRES,
2	Switches	LEGRAND SWITCHES (Electrical point As Per Design)
	LIGHTS	
1	Lights	CROMPTON OR ORIENT Panel Light + Cob lights + Profile Light
	PAINTS	
2	Paints:	ASIAN (Luster with Wall Putty, Primer +2 Coat)

1. Design & Execution:

- 2D & 3D Designing & Visualization
- Material Selection Assistance
- On-site Supervision
- Installation & Finishing Work

• Project Timeline: 60–65 Days

2. Why Choose Vistara Interiors?

• Transparent Pricing – No Hidden Charges

• High-Quality Materials & Craftsmanship

• Personalized Design with 3D Views

• 10-Year Warranty on Workmanship

• Professional Team with End-to-End Support

• Deep Cleaning will provided by us

• All Furniture Edge Work Will Be Done In Laminate Marching PVC Edge Binds to Ensure Smooth Edges and Seamless Finishing

Terms & Conditions:

Quotation subject to revision based on final 3D design.

Standard wardrobe modules included; extra drawers at additional cost.

Warranty will not be applicable for physical damage.

THANK YOU!

For any queries, feel free to contact us.

TEAM VISTARA INTERIORS

VISTARA